

United States Department of the Interior
National Park Service

For NPS use only

National Register of Historic Places
Inventory—Nomination Form

received

date entered 1/21/88

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic United States Post Office and Courthouse

and or common Caldwell Street Post Office

2. Location

street & number 102 Main Street

N/A not for publication

city, town Rock Hill

N/A vicinity of

state South Carolina

code 045

county York

code 091

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input checked="" type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input checked="" type="checkbox"/> government
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
		<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input type="checkbox"/> private residence
			<input type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input checked="" type="checkbox"/> other: Offices

4. Owner of Property

name City of Rock Hill

street & number 155 Johnston Street

city, town Rock Hill

N/A vicinity of

state South Carolina 29730

5. Location of Legal Description

courthouse, registry of deeds, etc. York County Courthouse

street & number 1 South Congress Street

city, town York

state South Carolina 29745

6. Representation in Existing Surveys

title South Carolina Inventory of
Historic Places

has this property been determined eligible? yes no

date 1986

federal state county local

depository for survey records South Carolina Department of Archives and History

city, town Columbia

state South Carolina 29211

7. Description

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

The United States Post Office and Courthouse is situated on a rectangular lot at the northeast corner of Caldwell and Main Streets in Rock Hill, York County, South Carolina. The three-story, brick and stone classically-detailed building was constructed in 1931-1932. Well-maintained, and with only minor alterations, the Post Office and Courthouse is an important element in the fabric of the city's central business district.

Additional Information

The United States Post Office and Courthouse sits slightly back from the corner of Main and Caldwell Streets, its long axis paralleling Caldwell Street. On the street sides, a narrow strip of lawn with small bushes separates the building from the sidewalk. On the east, or rear elevation, a similar strip of lawn divides it from the driveway that runs along the rear property line. At the north end, a larger area of lawn leads from the street back to the loading dock, with the area in front of the loading dock and at the north end of the property taken up by a driveway and small parking lot.


Rectangular in plan, the three-story building has a low, pink granite podium, a rusticated limestone first floor, and two stories of yellow pressed brick in running bond, topped with a limestone entablature. On the south, east and west elevations, the parapet is composed of regularly-spaced panelled limestone pedestals with turned limestone balusters between them. On the north elevation the parapet is continuous.

Of the two street elevations, the five-bay south (Main Street) elevation is the more ornate, though in terms of the plan it is a secondary entrance. The central three bays project slightly, defining a frontispiece. A wide, short flight of pink granite steps between the projecting arms of the podium rises to a small platform in front of the central entrance. On either side of the stair are free-standing, ornamented bronze classical light standards. Above the podium is a dado of ashlar limestone, capped by a limestone watertable. The rest of the first floor wall is rusticated limestone in courses, at the top of which is a flat limestone belt course with shallow relief carving in a running wave motif. The two outer bay windows on the first floor are larger, with eight over eight metal sash and four-light transoms. The inner bay windows are smaller, six over six windows.

The entrance surround has a double architrave, over which is a flat pediment supported by consoles. Topping this pediment is a row of angular palmettes, with a stylized eagle in the center. The interior, tri-partite shouldered architrave is enriched with bead and reel moldings and a backband of water-leaf. In the frieze over the architrave is a relief bundle of fasces, richly carved. A pair of multi-paned bronze and glass doors, ornamented with bosses and flanked by bronze pilasters, is surmounted by a bronze-screened transom.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**



U. S. Post Office and Courthouse

Continuation sheet Description

Item number 7

Page 1

On the second and third levels, the outer windows are in two-story bays with a plain metal spandrel between them and a plain limestone panel above. All sash on these levels are eight over eight. The central three bays are contained by two engaged Roman Ionic columns in antis between panelled antae. The recessed wall area between the columns is flat limestone ashlar with two-story window bays, the metal spandrel panels between the stories ornamented with wavy fluting and rosettes. Above each window panel is a low-relief limestone panel containing a swag.

The main entablature is a continuous limestone band broken only by the projection of the frontispiece. A tri-partite architrave is surmounted by a plain frieze, inscribed in deeply-cut letters on the frontispiece with "POST OFFICE AND COURTHOUSE." The cornice has a dentil course, base moldings and a fascia capped with a cyma recta molding. At the head of the frontispiece the cornice forms a closed pediment with a flat tympanum.

The seven-bay west (Caldwell Street) elevation is detailed on the first level like the south elevation, except that the inner four window bays have paired four over four windows with two-light transoms. At the second and third levels, the inner five bays are slightly recessed. Six-panelled, limestone antae define the window bays, each of which is composed of pairs of six over six sash with enriched metal spandrels between levels. Over the window bays are plain limestone panels. The outer window bays are like those of the south elevation outer bays.

Like the window bays below them, the central section of the entablature and parapet on the west elevation are recessed slightly. The frieze in this area is incised "UNITED STATES POST OFFICE AND COURTHOUSE."


At the opposite side of the building, the east elevation is also recessed in the central five bays on the second and third levels. However, this area is brick, with a single row of windows. The outer one on each end has ten over fifteen metal sash with ten light transoms, while the inner three windows are paired, with six over twelve sash and six light transoms. On the first floor the windows have eight over eight sash with four light transoms, except that the transoms have been replaced with metal louvers in the central four windows.

Least formal of the building's elevations is the north one. Its rusticated first floor runs halfway across, where it is interrupted by a projecting one and a half-story, three-bay, brick-faced pavilion. A plain limestone belt course

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

U. S. Post Office and Courthouse



Continuation sheet Description

Item number 7

Page 2

continues the carved belt course of the main block around this pavilion. Across the end of the pavilion is a metal-canopied loading dock. Under the canopy, the brick wall has been painted. On the upper half story the pavilion has eight over eight sash, with paired six over six sash on the side elevations. The upper two stories of the north elevation have five evenly-spaced bays of eight over eight sash, except that there is a small four over four window on each level. A pair of small metal ducts, apparently added later, run from above the third floor down the northeast corner.

At the northeast corner of the roof, visible from the street, is a squat, square chimney of brick with limestone string courses. The sides of the chimney have louvered metal vents and there is a circular sheetmetal cap on the top.

Interior

The principal interior space on the first floor is an L-shaped lobby that runs across the Caldwell street side and halfway down the Main Street side. This lobby, entered through a bronze airlock on the Caldwell Street side, contains the postal boxes, service windows, and stair to the second level. Throughout the lobby (and in corridors throughout the building), the floors are finished in terrazzo with marble borders, and there is a pink marble wainscot with red marble base. Marble is also used for classical door surrounds at the south end of the lobby. The walls are finished in smooth plaster with molded panels, and in the Caldwell Street section of the lobby, a plaster entablature delineates the upper, or transom area of the wall. Mahogany-finished wood is employed in the letter box bays and service window bays.

Most dramatic of the elements of the front lobby is the ceiling. Articulated into five bays by doubled beams supported on flat classical brackets, it is covered with embellished plaster coffers framed by courses of enriched moldings. Fluorescent lighting strips have been hung from the ceiling in recent years.

At the south, or Main Street end, the lobby is less opulently finished and has simple, panelled ceilings. The main decorative element in this area is the open stair, which rises in the southwest corner. Curving sinuously to the second floor, it has a bronze string and railings and pink marble steps.


Located at the southeast corner of the building, the Postmaster's suite consists of two rooms and a private toilet. The outer room has a panelled, mahogany-finished wainscot and crown mold, and the inner room contains a large wall safe.

The work rooms of the post office have a much more utilitarian finish than the rest of the building; high, tongue and groove wainscot and plain plaster walls.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

U. S. Post Office and Courthouse



Continuation sheet Description Item number 7 Page 3

A flight of stairs at the north end of the room leads up to a lounge and toilets, and there is an enclosed postal inspector's gallery that runs the length of the room.

Much of the second floor is taken up by the District Courtroom, centered at the rear of the building. Separated from it by a corridor running the length of the floor are suites of offices with plaster walls, maple floors and mahogany-finished door and window surrounds, baseboards and chair rails. At the north end of the hall are the Judge's Chambers, comprised of two large, connected rooms, one of which enters directly into the courtroom, and the judge's marble-wainscoted toilet. The judge's office has mahogany-finished panelled wood wainscot and plaster crown molding.

The courtroom itself is rectangular. Red gum panelling with a mahogany finish covers the lower three-quarters of the walls. The upper quarter is finished with a veneer of rusticated ashlar stone, now painted.

The ceiling is divided into five bays by large plaster beams supported by foliate consoles. Framing the flat area of the ceiling bays are richly embellished courses of plaster moldings. Each bay is divided into 390 square panels divided by foliate strips of fascias and each panel is ornamented with relief shells and foliage. At either end of every bay, the central panel has been replaced by a ceiling register. Strips of fluorescent lighting have also been mounted across the ceiling.

Two sets of double doors, covered on the inside with leather, open off the hall on one long wall. Above the doors are low-relief cartouches and swags. The other long wall contains five bays of windows.


At one end of the courtroom is spectator seating--three rows of moveable wooden benches which appear to be of later vintage than the courtroom. There are panelled doors in the rear wall leading to the witness and U.S. Marshall's rooms. A low, panelled partition with swinging doors sets apart the front two-thirds of the courtroom which contain the raised jury box at one side, the attorney's podium, the Clerk and Recorder's box, the witness stand and the judge's bench, all panelled in red gum with mahogany finish. Affixed to the counter at either end of the judge's bench is a bronze lamp with opalescent glass shade.

Behind the judge's bench is a classical frontispiece, a closed pediment and entablature supported by composite pilasters and engaged to columns in mahogany.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

U. S. Post Office and Courthouse



Continuation sheet Description Item number 7 Page 4

In the tympanum of the pediment is the inscription "Domina Justitia Qui Pro Sequitor." The wall surface directly behind the bench is panelled with pink marble in an enriched bronze frame.

Most of the third floor is taken up by the upper area of the courtroom, but a corridor running the length of the building gives access to suites of offices along the Caldwell Street side. These offices are simply-finished with plaster walls, maple floors and mahogany-finished wood trim.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input checked="" type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1931-32 **Builder/Architect** Batson-Cook Co./U.S. Supervising Architect's Office

Statement of Significance (in one paragraph)

The United States Post Office and Courthouse in Rock Hill, constructed in 1931-1932, is significant as an indicator of the population growth and commercial development of the city in the first third of the twentieth century. Its erection also reflects the rapid growth in Federal construction following the Public Buildings Act of 1926. The Post Office and Courthouse's carefully-composed classical exterior and richly-ornamented lobby and courtroom, designed by the Supervising Architect's Office of the Treasury Department, are distinctly superior to other buildings constructed in the area during the period.

Additional Information

Rock Hill's first post office was opened in 1852, the year the town was established. The location of the post office moved periodically over the next fifty years, generally occupying parts of other buildings.¹ However, by 1904 postal receipts had grown to \$20,000, spurring erection of the city's first Federal Building, which opened in 1906.² Its site, purchased for \$5,500, was at the edge of the central business district in a largely undeveloped area.³ One story tall, the building was constructed of red brick over a granite base, and had limestone and terra-cotta trim. Although there were larger commercial buildings in downtown, its Classical Revival design was in advance of anything in the city.

Construction of this new Federal building was symbolic of the growth of Rock Hill in the last quarter of the nineteenth century; from a crossroads to one of the fastest-developing cities in the South Carolina Piedmont. Incorporated in 1870 with 250 persons, by 1891 the population had increased to nearly 4,000. The first of a number of textile mills opened in 1880. Rock Hill was also home to the Rock Hill Buggy Company, later Anderson Motor Company, and to Winthrop Normal and Industrial College.⁴ Located directly on a major line of the Southern Railroad, the city was a natural center for the surrounding area.

This pattern of growth continued in the first third of the twentieth century. By 1930, the population had risen to 11,300, with 6,000 more people in the adjoining suburbs. Rock Hill was the largest city in York County, as well as in the adjacent three South Carolina counties. In addition to the retail business that came from the surrounding farming areas, cheap hydroelectric power helped lure industry such as the City's eight cotton mills, two yarn mills and hosiery mill, as well as one of the South's largest printing and finishing⁵ companies. (Now) Winthrop College's student population had risen to 1,800.

9. Major Bibliographical References

See continuation sheets

10. Geographical Data

Acreeage of nominated property less than 1 acre

Quadrangle name Rock Hill West, S.C.

Quadrangle scale 1: 24000

UTM References

A

1	7	4	97	6	4	0	3	8	6	4	5	2	0
Zone		Easting				Northing							

B

Zone		Easting				Northing							

C

Zone		Easting				Northing							

D

Zone		Easting				Northing							

E

Zone		Easting				Northing							

F

Zone		Easting				Northing							

G

Zone		Easting				Northing							

H

Zone		Easting				Northing							

Verbal boundary description and justification The boundary of the U.S. Post Office and Courthouse nomination is shown as the red line on the accompanying York County tax map, plat no. 101, map #627-16, which is drawn at a scale of 100 ft. to the inch. The nominated property includes the building and associated lot.

List all states and counties for properties overlapping state or county boundaries

state N/A code county N/A code

state N/A code county N/A code

11. Form Prepared By

name/title David R. and Allison Harris Black/Architectural Historians

organization Black & Black, Preservation Consultants date 29 May 1986

street & number 620 Wills Forest Street telephone (919) 828-4616

city or town Raleigh state North Carolina

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature

Mary W. Edmonds

Mary W. Edmonds

title Acting Deputy State Historic Preservation Officer

date

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

U. S. Post Office and Courthouse

For NPS use only
received
date entered

Continuation sheet Significance Item number 8 Page 1

As early as the mid-1920's, the need for a larger Federal building was perceived in Rock Hill. Congressman William F. Stevenson of Cheraw introduced a bill in the U.S. House of Representatives in 1925 which would have authorized the acquisition of a new Federal Building on a new site in Rock Hill.⁶ In the joint survey of public building needs carried out by the Post Office and Treasury Departments following passage of the Public Buildings Act of 1926, Rock Hill was one of two South Carolina cities where the need for a new Federal building was deemed urgent. The report estimated that an additional 2,240 square feet of post office space was required, and it noted that, "Although Federal courts are authorized to be held at Rock Hill, no Federal space⁷ is available, which fact makes it necessary for the courts to rent quarters".⁷

Under the series of public building funding authorizations from 1926 to 1931, \$300,000 was allocated for a new Federal building in Rock Hill.⁸ Plans were prepared by the Supervising Architect's Office in the Department of the Treasury under Acting Supervising Architect James A. Wetmore. Bids for the new Federal building were opened on June 3, 1931. Of the 21 bidders on the general contract, none was from South Carolina. The low bid was submitted by the Batson-Cook Company of West Point, Georgia, at \$175,773.⁹ Batson-Cook had carried out other Federal projects, and its superintendent for the Rock Hill work, S. L. Hodge, arrived directly from the completion of a new quarantine station in New Orleans.¹⁰ Batson-Cook's contract was for erection of the building itself. Plumbing and heating were installed separately by Waldrop Heating and Plumbing Company of Rock Hill, with still another contractor installing the elevator.¹¹

Additional land needed for the new building was acquired by condemnation in 1929 from the owners who had supplied the original lot. Its cost was \$21,300,¹² approximately four times the price of the initial site.


The first order of business in constructing the new post office was to remove the existing one. Only twenty-five years old, it was still one of the most substantial buildings in the city. The Federal government sold the old post office to the City of Rock Hill for a nominal sum, and it was placed on rollers and moved to the corner of Oakland Avenue and St. John's Court, where it was refurbished as the new public library.¹³ The building survives in good condition, but is no longer used for public purposes.

Excavation for the foundations began on July 8, 1931.¹⁴ By April of 1932, most of the exterior was complete and plastering of the interior had begun.¹⁵ It was anticipated that the building would be open well within the fourteen-month contract period. However, problems arose over the design of the ceiling in the lobby and over acoustical improvements proposed for the courtroom. The latter involved the use of a porous, "acoustical" stone facing for the upper part of

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

U. S. Post Office and Courthouse



Continuation sheet Significance Item number 8 Page 2

the courtroom wall. Although the Supervising Architect's Office approved these changes in August, the models for the ceiling design in the courtroom had to be sent back to Washington for reworking.¹⁶

At the end of November, the building was still not complete--the courtroom was unfinished, the stairway railing was not installed, the boiler was being altered, and the Postmaster's office furniture had not arrived. Nevertheless, the lease on the post office's temporary quarters was expiring, so the post office¹⁷ moved in over the weekend, opening for business on Monday, November 28, 1932.

The Rock Hill Evening Herald described the new building as "...handsome in every respect." Its first floor contained offices for the Postmaster and Assistant Postmaster, and the work room and service windows. In the basement were storage rooms and offices for the county farm agent and home demonstration agent. On the second floor were located the Federal courtroom, offices of Judge J. Lyles Glenn, offices of the Clerk of Court and other Federal officers' quarters. Offices of the District Attorney, Internal Revenue Officer, Deputy Marshal,¹⁸ and rooms for the grand jury and witnesses were located on the third floor.

In 1932, the new Federal building was the most accomplished piece of architecture in the city. Two other, large commercial buildings put up during the 1920's, the brick and limestone Andrew Jackson Hotel, and the brick and terra-cotta Citizens Bank Building, could neither match it for sophistication of design nor consistent use of high-quality materials.

The first postmaster in the new building was A. R. Barrett, whose term expired with the inauguration of Franklin D. Roosevelt. A Dr. Williams acted as temporary postmaster for several months before being replaced by Col. L. C. McFadden in 1933. McFadden's tenure extended until 1952, when he was replaced by Tom Gettys. Gettys later represented Rock Hill in the United States House of Representatives. John J. Wise became¹⁹ postmaster in 1954, serving until 1971, when he was succeeded by J. W. Roof.


As had happened with the previous post office, the growth of postal business gradually exceeded the capacity of the existing facility. Substations and a parcel post processing plant were opened, but the change from foot to vehicle delivery overwhelmed the small parking area of the Caldwell Street site. With the Baptist Church flanking the building on its two rear sides, there was no room for expansion., A much larger, new post office was constructed²⁰ in an urban renewal area at the edge of downtown, opening September 7, 1971.

On September 5, 1986, the City of Rock Hill purchased the building from the United States Postal Service for \$280,000. Currently, the building's occupants include the local congressman's office, the York County Tourism and Convention Bureau, and the Rock Hill Arts Council.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

U. S. Post Office and Courthouse



Continuation sheet

Significance

Item number 8

Page 3


Footnotes

- 1 "Postal Receipts Show Rock Hill's Expansion," Rock Hill (S. C.) Evening Herald, 3 May 1952, n.p. (Clipping Files, York County Library).
- 2 Ibid.
- 3 York County Clerk of Court, deed book 22, p. 796.
- 4 "Half Century of Progress Noted by C. of C. Secty," Rock Hill Evening Herald, 28 July 1931, p. 1.
- 5 Ibid.
- 6 H. R. 5033, 69th Cong., 1st sess., (1925).
- 7 H. R. Doc. No. 651, 69th Cong., 2nd sess., 99 (1927).
- 8 H. R. Doc. No. 788, 71st Cong., 3rd sess., 18 (1931).
- 9 "Twenty-three Bid on Post Office to be Erected Here," Rock Hill Evening Herald, 2 June 1931, p. 1; and "Work on New Post Office Building to Commence Soon," Rock Hill Evening Herald, 4 June 1931, p. 1.
- 10 "Making Plans to Get Work Started on New Post Office," Rock Hill Evening Herald, 6 July 1931, p. 1.
- 11 "Get Contract for Heating-Plumbing in New Post Office," Rock Hill Evening Herald, 13 July 1931, p. 1.
- 12 York County Clerk of Court, deed book 72, p. 224.
- 13 "Work on New Post Office Building to Commence Soon," Rock Hill Evening Herald, 4 June 1931, p. 1.
- 14 "Excavating for New Post Office Has Been Started," Rock Hill Evening Herald, 9 July 1931, p. 1.
- 15 "New Post Office Nears Finish," Rock Hill Evening Herald, 19 April 1932, p. 1.
- 16 "Soon Finish Post Office," Rock Hill Evening Herald, 20 June 1932, p. 1; "To Make Change on Post Office," Rock Hill Evening Herald, 12 August 1932, p. 1; and "Finish Post Office in About 2 Months," Rock Hill Evening Herald, 16 August 1932, p. 1.

United States Department of the Interior
National Park Service

**National Register of Historic Places
Inventory—Nomination Form**

U. S. Post Office and Courthouse



Continuation sheet Significance Item number 8 Page 4

17 "Post Office to Move This Week," Rock Hill Evening Herald, 22 November 1932, p. 1; and "Postmaster Barrett has Charge of \$300,000 Plant," Rock Hill Evening Herald, 28 November 1932, p. 1.

18 Ibid.

19 Rock Hill City Directories, 1925-26 to 1955; and "Postmaster, 2 Key Aids Retiring After 100 Years Combined Service," Rock Hill Evening Herald, 16 December 1972, p. 1.

20 "Opening of New Post Office Set," Rock Hill Evening Herald, 6 September 1971, p. 1.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

U. S. Post Office and Courthouse

For NPS use only
received
date entered

Continuation sheet Bibliographical References Item number 9

Page 1

Rock Hill City Directories. 1925-1926 through 1955 volumes.

Rock Hill (S. C.) Evening Herald, May-July 1931; April-November 1932;
6 September 1971; 16 December 1972; and 1 March 1985.

U. S. Congress. House. A Bill to Authorize the Acquisition of a Site
and the Erection of a Federal Building at Rock Hill, S. C., and to Sell the
Present Site. H. R. 5033, 60th Cong., 1st sess., 1925.

U. S. Congress. House. Committee on Public Buildings and Grounds.
Construction of Public Buildings Outside the District of Columbia. Doc.
788, 71st Cong., 3rd sess., 1931.


U. S. Congress. House. Public Buildings: Joint Survey of the Minimum Needs of
the Country for Public Buildings Made by Direction of the Secretary of the
Treasury and the Postmaster General in Pursuance of Their Duties under the
Public Buildings Act of 1926 and Informally Presented to Congress for its
General Information. Doc. 651, 69th Cong., 2nd sess., 1927.

York County Library Clipping File. Material on Rock Hill Post Office.

York County Clerk of Court. Deed Records. York County Courthouse.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form




Continuation sheet Photographs Item number Page

1. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
View from southeast (South - principal facade)
2. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
View from southeast (at right is east elevation)
3. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
View from southwest (at left is west elevation)
4. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
View from northwest (at right is west elevation)
5. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
Detail of south elevation
6. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
Main lobby / First floor
7. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
District Courtroom / Second floor

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**



Continuation sheet Photographs (continued) Item number Page

8. U. S. Post Office and Courthouse
York County, S. C.
John Marshall, August 8, 1987
City of Rock Hill/Planning Dept.
Rock Hill, S. C.
Detail of Courtroom ceiling

United States Post Office and
Courthouse
Main and Caldwell Streets
Rock Hill, S.C. York County
By: City of Rock Hill



2

2-B

JOHN'S CT.

OAKLAND

CALDWELL STREET

AVE.

